BRUHAT BANGALORE MAHANAGARA PALIKE

ind Venugopalswamy temple in ward no. 10 (Doc

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Providing Covering slabs for Existing drains behind Venugopalswamy temple in ward no. 10 (Doddabommasandra), Vidyaranyapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K V SUBBA REDDY	
				In Figures	In Words
1	169.2	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	95.25	Rupees Ninety Five and Twenty Five Paise Only
2	49.2	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4504.95	Rupees Four Thousand Five Hundred Four and Ninety Five Paise Only
3	705	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	284.61	Rupees Two Hundred Eighty Four and Sixty One Paise Only
4	125.6	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. etc complete as per specifications and directions of engineer in charge of the work	Cum	5921.18	Rupees Five Thousand Nine Hundred Twenty One and Eighteen Paise Only
5	113.04	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	qtl	7822.72	Rupees Seven Thousand Eight Hundred Twenty Two and Seventy Two Paise Only
6	135.36	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	76.34	Rupees Seventy Six and Thirty Four Paise Only

K V Subba Reddy

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92